Application Summary

We are pleased to present for your consideration the application for State of Good Repair for Federal Str. No. 2320. The following items are included in this application:

- Project Narrative
- SGR Pre-Scoping PowerPoint
 - Cost Estimate Summary
 - Bridge Quote
 - Structure Information
- Existing Bridge Plans (only plan view and deck section shown due to CII-SII)
 - Latest Bridge Safety Inspection Report (not included due to CII-SII)
 - Bridge Signage Form
- Example Bridge Plans (only plan view and deck section shown due to CII-SII)

VIRGINIA DEPARTMENT OF TRANSPORTATION PROJECT REVIEW COMMENT AND RESOLUTION SHEET

REVIEWER CODES:

- A. REQUIRED TO BE ADDRESSED. SIGNIFICANT ISSUE.
- B. REQUIRED TO BE ADDRESSED. POTENTIAL SIGNIFICANT ISSUE.
- C. SHOULD OR RECOMMENDED TO BE ADDRESSED.
- D. GOOD PRACTICE. COULD BE ADDRESSED
- E. BEST PRACTICE. COULD BE ADDRESSED

Scor	PE OF WORK: TRUSS REPLACEN	IENT	UPC NUMBER: N/A		FEDERAL STRUCTURE ID: 2320	DATE: VARIES PER BELOW	
DESC	RIPTION: RTE. 778 OVER MIDDI	LE RIVER	REVIEW PHASE: PRE-SCOPING/FUNDING		DISCIPLINE: VARIOUS – SEE BELOW		
No.	DOCUMENT ⁽¹⁾⁽⁴⁾	MENT ⁽¹⁾⁽⁴⁾ REVIEWER / DATE / COMMENT ⁽⁴⁾⁽⁵⁾		CODE ⁽⁴⁾	DATE / RESPON	SE ⁽²⁾	
4	Pre-Scoping powerpoint	BMPA (2/3/2021) Comment: Per the requirements on the SGR bridge webpage, please provide the alterative analysis per Chapter 32 of the Manual of the Structure and Bridge Division to determine the proposed bridge scope alternative (bridge replacement, deck replacement, superstructure replacement, minor bridge rehabilitation, culvert rehabilitation, culvert replacement). Another option, if applicable to not providing an alternative analysis, is to please expand on the presence of mitigating factors per S&B Manual 32.02-1 (sheet 1 of 4) that justify a replacement without providing an alternative analysis. Please use information such as settlement or scour defects, scour rating, waterway adequacy rating, etc."		В	PM/Designer (02/12/2021): Chapter 32 alternative analysis was not formally conducted due to the following: Preliminary study completed by the District verified that the existis superstructure is Fracture Critical. Per Part 2 Chapter 32.02-01, the mitigation factor alone warrants replacement. Existing Substructure components (Rated: 6) were concluded to be structurally sound an salvageable with minor rehab/retrofit work and does not warrant a replacement. PM/Designer (02/09/2021): Cross sections will be provided during the provided during		
5	Pre-Scoping powerpoint	provide proposed existing immediate approach roadv BMPA (3/2/21) IIM-LD-260/IIM-IID-11 r for the project cost estimate and that "all items assume	requires that "All assumptions te shall be clearly documented" at to be covered by the cost in the stated assumptions." GGR bridge projects were	В	PM/Designer (02/09/2021): Cross secti Phase. If project is not selected for SYII transverse sections will be provided for GS-4 (Rural local road) typical section v proposed approach estimate.	PFY2022-2027 cycle, next round.	

- (1) Indicate document reviewed or use "G" for general comment.
- (2) To be filled out by Project Manager in conjunction with Designer.
- (3) To be filled out by Reviewer based on review by Project Manager and Reviewer (list date resolved).

- (4) To be filled out by Reviewer.
- (5) Provide name of reviewer and the date of the comment.

Mutual resolution requires concurrence by BOTH the Project Manager and the Reviewer.

DATE: VADIES DED BELOW

VIRGINIA DEPARTMENT OF TRANSPORTATION PROJECT REVIEW COMMENT AND RESOLUTION SHEET

REVIEWER CODES:

- A. REQUIRED TO BE ADDRESSED. SIGNIFICANT ISSUE.
- B. REQUIRED TO BE ADDRESSED. POTENTIAL SIGNIFICANT ISSUE.
- C. Should or Recommended to be Addressed.
- D. GOOD PRACTICE. COULD BE ADDRESSED
- E. BEST PRACTICE. COULD BE ADDRESSED

SCOPE OF WORK: TRUSS REPLACEMENT		IPC NUMBER: N/A		FEDERAL STRUCTURE ID: 2320	DATE: VARIES PER BELOW		
DESC	RIPTION: RTE. 778 OVER MIDD	LE RIVER	REVIEW PHASE: PRE-SCOPING/FO	UNDING	DISCIPLINE: VARIOUS – SEE BELOW REVIEW TYPE: QA REVI		
No.	DOCUMENT ⁽¹⁾⁽⁴⁾	Reviewer / D	ATE / COMMENT ⁽⁴⁾⁽⁵⁾	CODE ⁽⁴⁾	DATE / RESPONSE ⁽²⁾		
6	Cost estimate workbook	now, please modify you phase starting in FY202 IID. Once we determine provided, we can allow work with you to adjust advise on district priorit	for an earlier schedule and /reduce inflation. Please	В	PM/Designer (02/16/2021): Accepted; Proposed project schedule has been revised and follows the practice outlined in the IIM. Proposed PE Phase start date is FY2026 (07/01/2025). RW and CN Phases have been revised. Note: Recommend not to move the AD date for the following reasons: This project currently ranks high in District's priority list. Existing structure is fracture critical and is rated as structurally deficient. Bridge was recently reopen and posted for 3 TON limit. This clarification has been added to the pre-scoping powerpoint.	 BMPA (3/2/2021): We will do our best to work with the district during programming to advance schedule but this will be a function of available SGR district funding. The district can consider the following: a district engineer exception request to prioritize this bridge ahead of other bridges. delaying less critical existing SGR projects. using M&O funds if there are safety concerns to maintain the bridge in safe condition until the bridge can be rehabilitated or replaced. 	

- (1) Indicate document reviewed or use "G" for general comment.
- (2) To be filled out by Project Manager in conjunction with Designer.
- (3) To be filled out by Reviewer based on review by Project Manager and Reviewer (list date resolved).

- (4) To be filled out by Reviewer.
- (5) Provide name of reviewer and the date of the comment.

Mutual resolution requires concurrence by BOTH the Project Manager and the Reviewer.

VIRGINIA DEPARTMENT OF TRANSPORTATION PROJECT REVIEW COMMENT AND RESOLUTION SHEET

REVIEWER CODES:

- A. REQUIRED TO BE ADDRESSED. SIGNIFICANT ISSUE.
- B. REQUIRED TO BE ADDRESSED. POTENTIAL SIGNIFICANT ISSUE.
- C. Should or Recommended to be Addressed.
- D. GOOD PRACTICE. COULD BE ADDRESSED

	Col	MMENT AND RESOLUT	TION SHEET		E. BEST PRACTICE. COULD BE ADDRESSED	—		
Scor	PE OF WORK: TRUSS REPLACE	EMENT	UPC NUMBER: N/A		FEDERAL STRUCTURE ID: 2320	DATE: VARIES PER BELOW		
DESC	CRIPTION: RTE. 778 OVER MID	DLE R IVER	REVIEW PHASE: PRE-SCOPING/F	UNDING	DISCIPLINE: VARIOUS - SEE BELOW	REVIEW TYPE: QA REVIEW		
No.	DOCUMENT ⁽¹⁾⁽⁴⁾	Reviewer / D	ATE / COMMENT ⁽⁴⁾⁽⁵⁾	CODE ⁽⁴⁾	DATE / RESPO	DATE / RESPONSE ⁽²⁾		
14	Narrative Cost estimate	truss bridge? Why used fra Can a conventional bridge BMPA (02/04/21): In the bridge replacement, please the use of a truss bridge. If a Design Waiver is requobtain (at least in concept) the documentation for this Checked our design man Fracture Critical structures. The current ADT is 290 (2) The Design ADT year strequesting the future ADT not sure what is the ADT ADT was 292. ADT has design the convention of the control of the control of the current ADT and the control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are control of the current ADT and the current ADT are current ADT are current ADT are current ADT and the current ADT are current ADT are current ADT and the current ADT are current ADT are current ADT and the current ADT are curren	ual and it is permitted to use when the ADT is less than 400. 2019 traffic data). hould be 2032. In addition to from Planning Division, I am will be in 2032. But the 2013 dropped. Being the rural area, It ADT will not be higher than the		PM/Designer (02/12/2021): Agreed. Traffic Data reports for Rte. 778: -2013: ADT of 290 (reported in 2019 re-2007: ADT of 320 -2001: ADT of 310 Bridge Structure query: ADT = 292 (20) Per Design Aids Part 2 Chapter 11.09-0 required on new trusses for projects with Using PCES Estimate Workbook v10.00 Design Year ADT = 2041 (Ad Date = F Design ADT = 350 (using current yr. A)	13) 1, a design waiver is not h Design ADT less than 400. 0, (Y30)		

- (1) Indicate document reviewed or use "G" for general comment.
- (2) To be filled out by Project Manager in conjunction with Designer.
- (3) To be filled out by Reviewer based on review by Project Manager and Reviewer (list date resolved).
- (4) To be filled out by Reviewer.
- (5) Provide name of reviewer and the date of the comment.

Mutual resolution requires concurrence by BOTH the Project Manager and the Reviewer.

Jamie Johnston 2/1/21

Project Narrative

Route 624 Back Creek (Pre-Scoping)

The purpose of this project is to replace an existing structurally deficient bridge and associated approaches on Route 624 with a new wider structure. The project is located in Augusta County approximately 0.7 miles east of the intersection with Route 664 in Lyndhurst. Route 624 (Mt. Torrey Road) is an urban minor arterial (GS-6) that is the crossroad at exit 91 on I-64. The area to the south of the project is populated with residential properties, to the northwest is a commercial warehouse, and to the northeast is a field. In 2018, the traffic count for Route 624 at this location was 3400 vehicles per days, with 7% trucks.

The width of the Route 624 approach roadway to the bridge is 24' (2 x 12' travel lanes) with 8ft shoulders, and it has a 45mph posted speed limit. The approach alignment contains a horizontal curve but constant roadway elevation. The existing two-lane 213'-0" long route 624 bridge, built in 1948, has a 5-span, 24ft wide (clear) concrete T-beam superstructure with a sufficiency rating of 17.2. The proposed two-lane 220'-0" long bridge will have a 2-span, 44'-0" wide (clear) steel girder superstructure.

Based on our documentation, the existing structure had grout bags added around pier 3 in or before 1990, and the streambed profile has been shown to be scouring around pier 3 over the last 50 years. Based on FHWA studies, pier scour countermeasures are only effective to a certain point; however, it is still susceptible to failure. The original plans show that the substructures are sitting on firm material, and it does not show existing piles. Our recent geotechnical borings from 2019 show no rock below the streambed for the complete length of the 195ft drilled so the assumption is that the existing bridge is not set rock. Based on the District institutional knowledge of the structure, it is actively scouring and attempting to maintain / rehabilitate the existing substructures would continue its exposure to possible undermining and in turn continue exposing the travelling public to a safety issue. Friction piles will support the proposed replacement substructures. The substructure footing will be set at an elevation determined in the scour analysis. As an additional safety measure, the piles will also be designed for an unsupported length. According to the SGR submittal requirements, assessment of an alternative rehabilitation option is necessary using Chapter 32 of the Manual of the Structure and Bridge Division. The above condition presented of scour susceptibility was considered as mitigating factors noted in File No. 32.03-1 that led us to decide not to pursue the alternate maintenance option.

Jamie Johnston 2/1/21

The project cost is estimated to be:

PE	\$1,579,972
RW	\$213,680
CN	\$9,990,581
Total	\$11,784,233

This is based on \$3,404,054 line-item base bridge estimate, \$749,220 line-item base roadway estimate, \$50,000 in-plan utilities, \$511,000 temporary bridge, \$50,000 MOT, \$268,214 mobilization (\$80k + 5% of (Subtotal - \$1M)), 20% CEI, and \$75k incentive. This is combined with 30% contingency (closer to a low risk project due to increased information from preliminary survey / geotechnical / hydraulics) to form the CN total. Base PE is 20% of the base CN, to which medium risk 12% contingency is applied, and base RW is 150k, to which 20% estimated contingency is applied. 2.9% yearly inflation adjustment is then applied to each subtotal over the period of that phase from today (5 years for PE, 6 years for RW, and 8 years for CN). Estimate includes results from consultant review comments from January 2020.





SGR PRE-SCOPING: 0778-007-6149

Rte. 778 over Middle River – Truss Replacement

Bridge Fed ID: 02320



Staunton District Structure and Bridge

Project Description:

- In-kind truss replacement with abutment retrofit on Route 778 over Middle River in Augusta County.
- Replace superstructure with in-kind, galvanized truss superstructure with concrete deck.
- Rehab/repair existing abutments; seat retrofit required for proposed superstructure.
- Approach work within project limits (100 ft. from both approaches).

Scope Justification:

- Bridge was closed at the end of 2019. Then reopened in early 2020 after urgent repair work due to political pushback. Currently posted at 3 tons.
- Per Part 2 Design Aids, Chapter 32, Identifies mitigation factor: "Fracture critical superstructure elements" as justification for replacement.



Scope Justification (continue...):

- District S&B investigated and concluded that the existing substructure is salvageable.
 - Substructure Rating: 6
 - No major concerns identified via 2020 Inspection Report.
 - No evidence of scour/settlement.
 - Scope of work includes rehab/repair of substructure elements.
 - Deemed structurally stable with proposed super configuration.
 - Does not warrant full-replacement.
- Existing bridge is eligible to received SGR funding as it meets both criteria per IIM-S&B-95.
- Per IIM-S&B-95, the scope of work for the proposed bridge project is eligible to received SGR funding as it achieves all three program requirements. Additionally, all scope elements identified in the pre-scoping document are covered under the list of qualifying work items eligible for reimbursement under the SGR program.



Significant Scope Elements:

• Overview: Existing truss has significant deterioration which required closing the bridge in 2019. Repairs were made in the following year to reopen the bridge and post at 3 tons.

Maintenance of Traffic:

- Existing bridge and section of Rte. 778 will be closed for construction.
- Traffic will be detoured via alternative route; Approx. 6.8 miles long.

Right-of-Way Impacts:

- Minimal RoW impacts are anticipated.
- Temp. Easement may be required for truss erection/unloading.

Utility and Environmental Impacts and Permits:

Unknown at this time. Will be investigated during PE Phase.



Significant Scope Elements (continue...):

Stakeholders:

- Locality High political push back to keep the bridge open.
- Additional Stakeholders and details to be determine in RW Phase.

Complex Project Elements:

Truss design and fabrication meets Agency's standards and specifications.

Hydraulic Impacts:

Not anticipated. Existing low cord will be maintained for HERS condition.

Risk Assessment:

- Truss design/details must meet Agency's standards/specs.
- Design waiver required for non-standard bridge roadway clear width
- Hydraulics Maintain existing low cord to eliminate hydraulic impact.



Project Cost Estimate:

Considerations:

- Truss replacement based on Cost/SF of similar project, inflated to estimate date.
- Quote from U.S Bridge used to support SF estimate. Price was increased to account for unloading, assembly, and installation of proposed truss.
- 8" Concrete deck with Class A4 concrete.
- Abutment reconstruction/retrofit design based on previous modifications used for similar rehab project (Contract ID No.: CM804BRA39606).
- GS-4 Standards for roadway approach, approximately 100 ft. prior to both approaches with full depth milling.



- Project Cost Estimate (continue...):
 - Contingency / Risk:
 - 10% Contingency used for PE relative to low risk associated with scope of work.
 - 25% Contingency used for CN on Bridge related costs relative to low risk.
 - 35% Contingency for Road Way CN Cost, as requested from L&D Designer.
 - Proposed Schedule: Project ranks high on District's priority list and is anticipated to be funded and started quickly. Existing structure is fracture critical, structurally deficient and recently reopened at 3 ton posting.

- Project Cost Estimate (continue...):
 - Inflation:
 - 29.47% Inflation factor (anticipated AD Date of FY30) applied to total Project CN Cost.
 - Obtained from VDOT's PCES Spreadsheet v10.00
 - 3.00% Inflation rate (typ.) per yr. for PE Phase Cost (Start Date: 07/01/2025)
 - 3.00% Inflation rate (typ.) per yr. for RW Phase Cost (Start Date: 07/01/2027)



SMART FLAG(S) – SUPPORTING DOCS.

Fracture Critical Member

- Advanced section loss.
- Superstructure Rating: 4.
- Bridge is posted at 3 tons.

Replace Existing Truss with In-Kind Truss

- Low cost option
- ADT < 300 (2013)
- Roadway Classification: Rural Local Road



PROJECT COST ESTIMATE SUMMARY

Project Estimate:

Preliminary Engineering					
Project Estimate (Component		Propo:	sed Project Cost	Estimate (\$)
Discipline	Source	E	Base (\$)	Contingency (%)	Total
Roadway	Profess. Judgement	\$	96,944	12.00%	\$108,577
Hydraulics	Profess. Judgement	\$	15,000	12.00%	\$16,800
In-plan Utilities	Profess. Judgement				\$0
Traffic	Profess. Judgement	\$	15,000	12.00%	\$16,800
Structures/Bridges	Profess. Judgement	\$	224,561	12.00%	\$251,508
Materials/Geotech	Profess. Judgement	\$	15,000	12.00%	\$16,800
Survey	Profess. Judgement	\$	30,000	10.00%	\$33,000
Environmental	Profess. Judgement	\$	75,000	15.00%	\$86,250
Right of ∀ay	Profess. Judgement	\$	10,000	12.00%	\$11,200
Other					\$0
	YDOT Oversight Costs				\$0
Total PE Phase Estimate			481,505	12.34%	\$540,935
	Inflation factor (%)		3.0%		\$78,033.85
To	tal Inflated PE Estimate				\$618,969
PE Base Estimate Da	ate (XX/XXXX)		12/10/2020		
PE Phase Start Date	(XXIXXIXXXX)		7/1/2025		
Right-of-Way & Utilities					
Discipline	Source	E	Base (\$)	Contingency (%)	Total
Right-of- V ay	Aerial Photo		\$40,000	50.00%	\$60,000
Out-of-Plan Utilities (power, cable, gas, etc.)					\$0
	VDOT Oversight Costs				\$0
T ₁	otal R V Phase Estimate		\$40,000	50.00%	\$60,000
	Inflation factor (%)		3.0%		\$12,836.55
То	tal Inflated R V Estimate				\$72,837
Base Estimate Date	e (XX/XXXX)		Dec-20		
R¥ Phase Start Date	(XXIXXIXXXX)		7/1/2027		

Discipline	Source	Base (\$)	Contingency (%)	Total
Mobilization	Profess, Judgement	\$100,000	40.00%	\$140,000
мот	Profess, Judgement	\$50,000	40.00%	\$70,000
Roadway	Profess, Judgement	\$323,146	40.00%	\$452,404
Hydraulics	Profess. Judgement			\$0
In-plan Utilities	Profess. Judgement			\$0
Traffic	Profess. Judgement	\$30,000	40.00%	\$42,000
Structures/Bridges	Similar Project	\$1,122,805	40.00%	\$1,571,927
Materials/Geotech	Profess. Judgement			\$0
Soundwalls	Profess. Judgement			\$0
Other				\$0
	Total Bid Items	\$1,625,951	40.00%	\$2,276,331
Incidental - Claims & Vork Orders (5% to 10% max)	5%	\$81,297.54	40.00%	\$113,816.55
ilroad Flagging/Coordination	n e			0
State Forces				0
State Police				0
Contract Requirements (Incentive)	5%	\$81,297.54	40.00%	\$113,816.55
	Environmental Inspection (\$)			0
Construction Engineering	VDOT or Locality (\$)	\$ 351,041.82	40.00%	\$491,458.55
(Inspection)	YDOT Oversight (\$)		000	0
	Total CEI			\$491,458.55
1	otal CN Phase Estimate	\$2,139,588	40.00%	\$2,995,423
	Inflation factor (%)			\$882,751
Total Infl	ated CN Phase Estimate			\$3,878,174
CN Base Estimate D	ate (XX/XXXX)	Dec-20		
CN Phase Start Date	(XX/XX/XXXX)	8/1/2029		
CN Phase End Date	(XXIXXIXXXX)	12/1/2030		
Total Project Co	st Estimate			\$4,569,979




SITE PLAN - EXISTING ARIAL IMAGE

Conceptual Site Plan: Replace in kind




PRE-SCOPING: EXISTING BRIDGE SECTION





PRE-SCOPING: PROPOSED TRANSVERSE SECTION





SYIP PROJECTS

	SYIP PRO DETAILED PROJECT COST		DV	
	(Version: 11		Λ1	
Portal ID:	Route 778 over Mid		Project UPC:	117024
Prepared By:	Alex Bellido		Milestone	Creation/Pre Scope
Reviewed By:	Eulogion "Jo" Ja		Date:	2/12/2021
County/City/Town:	Augusta County	(07)	Tier Level	1
Preliminary Engineering		1		
Project Estimate Co	mponent	Р	roposed Project Cost Est	imate (\$)
Discipline	Source	Base (\$)	Contingency (%)	Total
Roadway	Profess. Judgement	\$ 96,944	12.00%	\$108,577
Hydraulics	Profess. Judgement	\$ 15,000	12.00%	\$16,800
In-plan Utilities	Profess. Judgement			\$0
Traffic	Profess. Judgement	\$ 15,000	12.00%	\$16,800
Structures/Bridges	Profess. Judgement	\$ 224,561 \$ 15,000	12.00% 12.00%	\$251,508
Materials/Geotech	Profess. Judgement	\$ 15,000 \$ 30,000	10.00%	\$16,800 \$33,000
Survey Environmental	Profess. Judgement Profess. Judgement	\$ 75,000	15.00%	\$86,250
Right of Way	Profess. Judgement	\$ 10,000	12.00%	\$11,200
Other	r roress. Judgement	Ψ 10,000	12.00%	\$0
0.1101	VDOT Oversight Costs			\$0
	Total PE Phase Estimate	\$ 481,505	12.34%	\$540,935
	Inflation factor (%)	3.0%		\$78,033.85
	Total Inflated PE Estimate			\$618,969
PE Base Estimate Date	e (XX/XXXX)	12/10/2020		
PE Phase Start Date (X	X/XX/XXXX)	7/1/2025		
Right-of-Way & Utilities				
Discipline	Source	Base (\$)	Contingency (%)	Total
Right-of-Way	Aerial Photo	\$40,000	50.00%	\$60,000
Out-of-Plan Utilities	Acriair noto	7.15/555		
(power, cable, gas, etc.)				\$0
	VDOT Oversight Costs			\$0
	Total RW Phase Estimate	\$40,000	50.00%	\$60,000
	Inflation factor (%)	3.0%		\$12,836.55
	Total Inflated RW Estimate			\$72,837
Base Estimate Date		Dec-20		
RW Phase Start Date ()	(X/XX/XXXX)	7/1/2027		
Construction			-	
Discipline	Source	Base (\$)	Contingency (%)	Total
Mobilization	Profess. Judgement	\$100,000	40.00%	\$140,000
MOT Roadway	Profess. Judgement Profess. Judgement	\$50,000 \$323,146	40.00% 40.00%	\$70,000 \$452,404
Hydraulics	Profess. Judgement	\$323,140	40.00%	\$432,404
In-plan Utilities	Profess. Judgement			\$0
Traffic	Profess. Judgement	\$30,000	40.00%	\$42,000
Structures/Bridges Materials/Geotech	Similar Project Profess. Judgement	\$1,122,805	40.00%	\$1,571,927 \$0
Soundwalls	Profess. Judgement			\$0
Other				\$0
Incidental Claims 9 Mark Orders (50/ to	Total Bid Items	\$1,625,951	40.00%	\$2,276,331
Incidental - Claims & Work Orders (5% to 10% max)	5%	\$81,297.54	40.00%	\$113,816.55
Railroad Flagging/Coordination				0
State Forces State Police				0
Contract Requirements	_			· · · · · · · · · · · · · · · · · · ·
(Incentive/Disincentive)	5%	\$81,297.54	40.00%	\$113,816.55
	Environmental Inspection (\$)	A 6-1-1-1	40.0-**	0
Construction Engineering (Inspection)	VDOT or Locality (\$) VDOT Oversight (\$)	\$ 351,041.82	40.00%	\$491,458.55 0
	Total CEI			\$491,458.55
	Total CN Phase Estimate		40.00%	\$2,995,423
	Inflation factor (%)			\$882,751
AND 5" . 5	Total Inflated CN Phase Estimate			\$3,878,174
CN Base Estimate Dat CN Phase Start Date (λ		Dec-20 8/1/2029		
CN Phase End Date (X		12/1/2030		
Total Project Cost	Estimate			\$4,569,979

SYIP Total Project Cost Estimate Summary Comparrison Between Consultant and Agency												
Phase		Base (\$) *			Contingency (\$)	*		Inflation (\$)	**	Total ***		
PHase	VDOT	Consultant	Diff. (+/-)	VDOT	Consultant	Diff. (+/-)	VDOT	Consultant	Diff. (+/-)	VDOT	Consultant	Diff. (+/-)
PE Phase Estimate	\$ 482 K	\$ 615 K	\$ 133 K	\$ 59 K	\$ 86 K	\$ 27 K	\$ 78 K	\$ 104 K	\$ 26 K	\$ 619 K	\$ 805 K	\$ 186 K
RW Phase Estimate	\$ 40 K	\$ 0 K	-\$ 40 K	\$ 20 K	\$ 0 K	-\$ 20 K	\$ 13 K	\$ 0 K	-\$ 13 K	\$ 73 K	\$ 0 K	-\$ 73 K
CN Phase Estimate	\$ 2,140 K	\$ 2,021 K	-\$ 118 K	\$ 856 K	\$ 911 K	\$ 55 K	\$ 883 K	\$ 864 K	-\$ 19 K	\$ 3,878 K	\$ 3,797 K	-\$ 82 K
Total Estimate	\$ 2,661 K	\$ 2,636 K	-\$ 25 K	\$ 935 K	\$ 997 K	\$ 62 K	\$ 974 K	\$ 968 K	-\$ 6 K	\$ 4,570 K	\$ 4,601 K	\$ 31 K



AISC Advance Bridge Certification (ABR)

201 Wheeling Avenue, P.O. Box 757 Cambridge, OH 43725, 1 (888) 872-7434

www.usbridge.com

To: VDOT – Staunton District

Attn.: Mr. Alex Bellido

811 Commerce Road, Staunton, VA 24401

Phone: (540) 569-4520

Project: Augusta Co., VA

Route 778

Price: \$415,000.00

U.S. Bridge Contact: Brian Mergenthaler

412-445-7661

bmergenthaler@usbridge.com

Estimate No: E1806028

Quotation Date: January 21, 2020

Page: 1 of 4

The following is a U.S. Bridge ENGINEER'S COST ESTIMATE for the subject project. This ESTIMATE is intended for preliminary estimating purposes only and should <u>not</u> be interpreted as a final QUOTATION. The information presented is based on the most current data made available to U.S. Bridge

Details:

Bridge length

Bridge roadway width

Bridge loading

Steel grade

Steel finish

Steel components

Bridge roadway flooring

Shear studs (shop attached)

Finished wearing surface

Timoriou wouling ouridoo

Bridge roadway railing

Bearing plates

Bearing pads

Assembly hardware

Anchor bolts

Freight to the site*

Skew

Design

Drawings stamped by PE in

Additional details

182'-0" c/c bearings

14'-6" c/w

HL-93

ASTM A709, Grade 50

Hot-dipped galvanized

See page 2

Stay-in-place forms, included

Included

8" Concrete by others

Thrie-beam, galvanized

Included

Included

Included

Included

See Page 2

N/A

Cambridge Flat Truss, All-bolted

Virginia

See Page 2



AISC Advance Bridge Certification (ABR)

201 Wheeling Avenue, P.O. Box 757 Cambridge, OH 43725, 1 (888) 872-7434 www.usbridge.com U.S. Bridge Contact: Brian Mergenthaler

412-445-7661

bmergenthaler@usbridge.com

Estimate No: E1806028

Quotation Date: January 21, 2020

Page: 2 of 4

ADDITIONAL DETAILS

COMPONENTS:

The bridge consists of two trusses and a floor system. Each truss will be shipped in four (4) sections. All steel to be unloaded, assembled and installed by others.

Please note that all sizes and weights are approximate and are subject to change. Final design drawings govern for weights and lifting points.

Pricing is based on steel cost as of January 20, 2020. Fluctuations of +/- 2% between time of quote and fabrication of bridges will necessitate a new quote.

FREIGHT: Shipment to the closest location (accessible by common carrier) for the loads described below has been included. Any deviation will result in additional freight charges to the customer. 8 over-dimensional load + 1 legal load.

TECHNICAL ASSISTANCE: On site technical assistance for three days (per span) for the installation of the U.S. Bridge products has been included. Advance notice of 30 days is required to schedule this assistance. Additional days can be provided for \$1,000/day.

DELIVERY: Tentatively, 8-10 weeks after drawing approval, subject to material and freight availability, and backlog.

PAYMENT: 30% due upon receipt of order

30% due upon completion of fabrication

30% due prior delivery to site

Balance due the earlier of last shipment or 30 days after completion of fabrication

EXCLUDED: All items not specifically listed above. Sales tax has been excluded.

TERMS AND CONDITIONS OF SALE: Page 3

BUYER:	U.S. BRIDGE:
	R. 6.:
Authorized Signature:	Authorized Signature:
Name & Title:	Name Printed: Dan Rogovin, President
Date & P.O.#:	Date: January 21, 2020



AISC Advance Bridge Certification (ABR)

201 Wheeling Avenue, P.O. Box 757 Cambridge, OH 43725, 1 (888) 872-7434 www.usbridge.com U.S. Bridge Contact: Brian Mergenthaler

412-445-7661

bmergenthaler@usbridge.com

Estimate No: E1806028

Quotation Date: January 21, 2020

Page: 3 of 4

U.S. BRIDGE TERMS AND CONDITIONS OF SALE

- **1. DEFINITIONS.** U.S. Bridge is the "Seller" and the customer is the "Buyer". The materials and, if applicable, the construction work ("work") sold by the Seller to the Buyer are the "Project".
- 2. ENTIRE AGREEMENT. These terms and the terms of Seller's quotation are the entire contract between the parties with respect to the Project, replace all prior agreements, oral or written, and may only be amended in a writing signed by the parties. If Buyer submits its own purchase order or other document, Seller objects to any terms that are additional or different from Seller's terms unless Seller expressly accepts each such term separately in writing. Delivery of materials and/or performance of work by Seller shall not be deemed to be such acceptance.
- 3. COST INCREASES. Seller's price may be increased to reflect increases in Seller's cost for materials ordered specifically to fill Buyer's order.
- 4. P.E. STAMPED DOCUMENTS. All documents bearing the stamp of a registered professional engineer that are submitted by Seller to Buyer in connection with the Project remain the property of Seller and may not be changed, transferred to third parties, nor used for any purpose other than the Project without Seller's express written consent.
- 5. FOB; TAXES; INVOICE; PAYMENT. Unless otherwise specified by Seller in writing: (a) any separate contract price for Seller's materials is FOB Project site, where title and risk of loss shall pass upon full payment by Buyer; (b) applicable sales taxes are not included in the price and are due absent a legal tax exemption certificate; (c) Seller's invoices shall be paid when due or shall accrue interest of one and one-half percent (1.5%) per month; (d) Seller may hold its materials as security for payments due or past due and invoice storage charges of one and one half percent (1 ½%) of the contract price per month which shall extend the final delivery date. Completed bridges not released for shipment within 30 days of completion of fabrication shall incur storage fees equal to one and one half percent (1 ½%) of the contract price per month.
- 6. WARRANTIES. Unless otherwise specified by Seller in writing, all of Seller's warranties on materials are included in the document entitled "One Year Limited Warranty" ("Warranty"), the terms being incorporated herein. If Seller is performing work as part of the Project, Seller also warrants that the work shall conform to the written plans and specifications in all material respects, provided that Seller is not liable for errors made by Buyer or the Project owner therein. Buyer's remedies for breach of warranty shall be limited to the remedies in the Warranty.
- **7. DELAYS.** Seller shall not be liable for any delays due to Acts of God, accidents, labor or transportation problems, shortages of materials, Buyer's default, or any other cause beyond Seller's control.
- 8. RESPONSIBILITY, DAMAGES. Unless the Project includes work by Seller, (a) Buyer shall indemnify and hold Seller harmless against any property damage or personal injury caused by the handling and/or installation of Seller's materials, and (b) Seller's technical assistance during installation shall not be considered a professional service, shall not relieve Buyer of its sole responsibility for installation, and Seller shall have no liability by reason of such assistance. In no event and under no circumstances shall Seller be liable for any incidental, consequential, liquidated or punitive damages upon any claim arising out of the Project. Buyer shall not withhold payment or issue backcharges against Seller's invoices for any reason.
- 9. APPLICABLE LAW, ARBITRATION, POWER OF ATTORNEY. This contract shall be subject to Ohio law and any claim by either party shall be resolved solely by arbitration in Columbus, Ohio pursuant to the applicable rules of the American Arbitration Association. The prevailing party shall recover its costs and expenses of arbitration and collection including its reasonable attorney fees. In addition to arbitration, Buyer hereby appoints Seller its attorney in fact to collect from any third party sums due Buyer for work of which the Project is a part and to apply such sums to Buyer's account, Buyer remaining liable for the balance.
- 10. LIMITED WARRANTY. See page 4.



AISC Advance Bridge Certification (ABR)

201 Wheeling Avenue, P.O. Box 757 Cambridge, OH 43725, 1 (888) 872-7434 www.usbridge.com U.S. Bridge Contact: Brian Mergenthaler

412-445-7661

bmergenthaler@usbridge.com

Estimate No: E1806028


Quotation Date: January 21, 2020

Page: 4 of 4

ONE YEAR LIMITED WARRANTY

- 1. WARRANTY. US Bridge warrants to the ultimate owner (the "Owner") of its bridges and other bridge products (the "Products") that the Products will conform to all plans and specifications and will be free from defects in material or workmanship for one (1) year from the delivery date, subject to the terms and conditions herein.
- 2. CORROSION. U.S. Bridge is not responsible for any corrosion of steel if (a) de-icing materials are applied to the Products, or (b) paint properly applied by U.S. Bridge is not maintained. U.S. Bridge does not perform and therefore does not warrant any galvanizing. V & S Columbus Galvanizing LLC issues its own 35 year limited warranty which excludes galvanized bridge decks and pans.
- 3. **EXCLUSION**. The above limited warranty **excludes** all other warranties, express or implied, including but not limited to **the** implied warranties of merchantability and fitness for a particular purpose.
- **4. NOTICE OF DEFECTS.** The Products shall be inspected upon receipt and written notice shall be given of any visible defects together with photographic evidence. Where defects are not visible, written notice and photographic evidence shall be given within the 1-year warranty period. Time is of the essence.
- **5. CONDITIONS.** Damage to the Products caused by (a) unloading, storage, assembly or installation by others, (b) live loads in excess of design loads, impact or other abnormal conditions, or (c) alterations by others not authorized in writing shall void this warranty.
- **6. REMEDIES**. Owner's sole and exclusive remedy for breach of warranty is limited to U.S. Bridge's repair or replacement (at its option) of defective parts of the Products at the place of delivery or installation in the manner most cost-effective and in conformity with generally accepted engineering practices. U.S. Bridge shall not be liable for damages (whether compensatory, punitive, incidental, consequential or otherwise) for any defects, or the cost of any labor or material incurred without U.S. Bridge's written authority. The Owner shall provide all necessary access to the Products and all detours, safety and traffic controls without charge to U.S. Bridge.
- 7. APPLICABLE LAW AND ARBITRATION. This Warranty shall be construed in accordance with and governed by the laws of the state of Ohio. Any controversy or claim arising out of or relating to this Warranty, or the breach thereof, shall be settled by arbitration in Columbus, Ohio in accordance with the Commercial Arbitration Rules of the American Arbitration Association, and judgment upon the award may be entered in any court having jurisdiction thereof. The prevailing party shall recover its costs and expenses, including its reasonable attorney fees.

<u>Structure Information</u>



Click Here for Current Inspection Report



Database information was Updated from PONTIS on 12/10/2020


Code By Keith Weakley

RTE. 778 OVER MIDDLE RIVER


STR. 6149

AUGUSTA COUNTY

3-5-72 AW.S. Sheet 1 of 7



Note: All Stringers are continuous There are four splices in each stringer approx. 2'from F.B.




RTE 778 OVER MIDDLE R
AUGUSTA COUNTY
PROJECT 0778-007-6149, STR. NO 6149 RIVER

SRO

ORDER NO.: NJ2
CONTRACT ID. NO.: CM804BRA39606


ORDER NO.: NJ2 CONTRACT ID. NO.: CM804BRA39606



THHY

RTE 778 OVER MIDDLE RIVER AUGUSÍA COUNTY PROJECT 0778-007-6149, SROI STR. NO 6149

ORDER NO.: NJ2 CONTRACT ID. NO.: CM804BRA39606




TYPICAL TRANSVERSE SECTION


Note: Replacement members shall be not dipped galvanized. Remaining truss members shall be recoated.




RTE 778 OVER MIDDLE RIVER
AUGUSTA COUNTY
PROJECT 0778-007-6149, SR01
STR. NO 6149



Note the full Bridge Safety Inspection Report was included in the application. Due to CII, this report has not been included in this public sample application.





SUPERVISED: Eulogio :Javier II, PE

Jamie Johnston

DESIGNED: Jamie Johnston

CHECKED: Keith Harrop, P.E

STATE		FEDERAL A	AID		STATE		SHEET
STATE	ROUTE	PROJ	ECT	ROUTE	PROJECT	NO.	
VA.				733	0733-007-0	6127	I
NBIS	NBIS Number: 00000000002257			UPC	No.		
			Construction	X032-S	. 0		
Feder	Federal Oversight Code: N/A				Scour Code:	XU32-3	0

GENERAL NOTES:

Width: 13'-6" face-to-face of rails.

Span Layout: I - 73'-8" steel truss span.

Capacity: HL-93 loading.

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2007.

Design: AASHTO LRFD Bridge Design Specifications, 6th Edition, 2012; and Interim Specifications; and VDOT Modifications

Standards: Virginia Department of Transportation Road and Bridge Standards, 2008.

This project is to be constructed in accordance with the Virginia Department of Transportation Work Area Protection Manual, June 2011 and latest revisions.

Design loading includes 15 psf allowance for future wearing surface.

Concrete in the substructure shall be Class A4 having a minimum compressive cylinder strength of 4 ksi at 28 days. Low permeability concrete shall be used in this project.

All reinforcing steels shall be CRR (corrosion resistant reinforcement) - low carbon/chromium and shall conform to the requirements of ASTM A-1035 and the applicable specifications in SBIIM 81. The minimum yield strength shall be: 100 ksi. Reinforcing Steel, Class II or Class III, may be be substituted for Class I. All dimensions on the detailed drawings are to centers of bars except where otherwise noted and are subject to fabrication and construction tolerances.

Bridge Number of existing structure is 6127. No existing plans.

Pony truss type and the number of panels may differ from that shown. Floorbeams shall be below bottom chords. Stringers shall rest on abutments. Stringers shall be continuous over two supports. Adjacent stringers shall not end on same floorbeam.

B.M. #1: Rebar Driven in Ground, 130' W of Abutment A Upstream Elevation (Top of Rebar) - 1341.47'

B.M. #2: Rebar Driven in Ground, 85' E of Abutment B Downstream Elevation (Top of Rebar) - 1343.67'

Work is to be performed by State Forces.

General notes continued on Sheet No. 2

One bolted field splice permitted.

VDOT

COMMONWEALTH OF VIRGINIA

DEPARTMENT OF TRANSPORTATION PROPOSED SUPERSTRUCTURE ON

RTE. 733 OVER ELK RUN
AUGUSTA CO. - 0.93 MI. NORTH OF RTE. 734

PROJ: 0733-007-6127

Sheet I of 5

Date: June 2015 © 2015, Commonwealth of Virginia

REVISIONS

Scale: $\frac{3}{16}$ "= 1'-0"